



Bæreevne
Bæresystem, inkl. tak: R 15 [B 15]

Informasjon
Risikoklasse: 3

Brannklasse: 1
Bruttoareal: ca. 415 m² (hovedbygg)
Personantall: ca. 40
Dører til rømningsvei skal ha fri bredde på minimum 0,86 meter (10X21M)

Branntekniske installasjoner
Heldekkende brannalarmanlegg (kategori 2), med akustiske og optiske signalgivere

Høytmonterte etterlysende markeringsskilt over rømningsdører og dører som inngår i fluktvei, samt nødbelysning

Annet
Tegningen er å anse som konsepttegning og skal leses sammen med brannkonseptet. Den har ikke status som byggetegning.

F0 2	2019-04-08	Anbudsunderlag/for uavhengig kontroll	AAMHA	HEL	AAMHA
B0 1	2019-03-25	For informasjon/kommentar hos eksterne parter	AAMHA	HEL	AAMHA
Revision	Date	Description	Prepared	DIC	Approved

This document has been prepared by Norconsult AS as part of the assignment stated below. Intellectual property rights belong to Norconsult AS. The document may only be used for the purpose stated in the contract between Norconsult AS and the client, and may not be copied or made available by other means or to a greater extent than the intended purpose requires.

Trysil Kommune

Scale: SIZE (gjelder A1)
1:100

Jordet barnehage, prosj. nr. 06341
Branntegning - snitt A-A

Vedlegg til brannkonsept F-001

Norconsult	Project number 5187924	Document number F-40-00-01	Revision F02
------------	---------------------------	-------------------------------	-----------------