

## Tranøy branngarasje - Lysarmaturer

Dato: 24.05.2019

Indeks	Antall	Produsent	Artikkelnavn	Tilbehør / kommentar	Artikkelnr	Bestykning	Lysstrøm	Kontakteffekt	Fargetemp.	Avdekning	Plassering
UP01	15	Glamox	MIRZ67-1500 LED 7500	montert under kabelbro	<a href="#">MIRO78923</a>	1xLED MIR 7500 840	7481 lm	60 W		4000 IP66	Garasje
UP01	4	Glamox	MIRZ67-1500 LED 7500	montert i tak	<a href="#">MIRO78923</a>	1xLED MIR 7500 840	7481 lm	60 W		4000 IP66	Garasje
UP02	16	ERCO	Skim Downlight 1xLED 8W		80292000	1xLED	758 lm	11 W		3000	Garderobes, VF
UP03	5	ERCO	Skim Downlight 1xLED 13W		80294000	1xLED	1087 lm	11 W		3000	Gard. Uren sone
UP04	3	ERCO	Compact Downlight 1xLED 8W		84425000	1xLED	728 lm	10W		3000 IP65	Dusj
UP05	2	Glamox	O70-S410 LED 1800 HF 840 BL		O70212202	1xR3300XL	2172 lm	30,2W		4000	Innganger
UP06	2	Norlux AS	Via 740 60-120° 53W Clear	inkl. veggbrakett	713-2-04-1	1xLED1x5900 T740	5897 lm	53 W		4000 IP66	over porter
UP07	5	Norlux AS	Via 740 60-120° 53W Clear	5 stolper 7m inkl. fundament	713-2-04-X	1xLED1x5900 T740	5897 lm	53 W		4000 IP66	langs vei
UP08	1	Glamox	i60-1200 LED 3600 HF SPR-SEN 840 OP	med sensor	<a href="#">I60091087</a>	1xLED	3857 lm	133 W		4000 IP44	Tekniskrom
UP09	3	Glamox	A40-600 LED 1000 HF 830 SMRB-SEN	med sensor	<a href="#">A40812267</a>	1xLED 1000		996 9 W		3000	WC
UP10	4	Glamox	A40-600 LED 1000 HF 830 OU	med stikk	<a href="#">A40812282</a>	1xLED 1000		996 9 W		3000	Gard