



LED LAMP G4 HALO-LED

344-25

LED-lamp with G4 cap. The colour temperature is warm white, 2800K and is dimmer compatible. The small size makes it suitable in many luminaires.

Specification

Logistical Information

Documents

Colour:	Transparent
Light Source Color:	Warm white
Width/length (cm):	1.00
Height (cm):	2.80
Depth (cm):	1.00
Number of Lamps:	1
Light Source Type:	LED
Cap/Socket:	G4
Color Temperature (K):	2800
Incandescent Equivalent:	11W
Luminous Flux (lm):	100
Color Rendering Index (CRI/Ra):	80
Colour Consistency (SDCM):	6
Average Life Time (h):	25000
Switch Cycles:	12500
Starting Time:	0 s
Operational Temperature Min/Max:	-20° - +40°
Power Factor:	0.780000
Lamp Current (mA):	120
Lamp Effect (W):	1,1
Lamp Voltage (V):	12VAC/DC
Energy Class:	A++
IP Class:	IP20



LED LAMP G9 HALO-LED

344-07

Illumination LED-lamp with a G9 cap. The bulb has frosted PC cover, the colour temperature is 2700K and it is dimmer compatible.

Specification

Logistical Information

Documents

Colour:	Frosted
Light Source Color:	Warm white
Width/length (cm):	1.65
Height (cm):	4.60
Depth (cm):	1.20
Number of Lamps:	1
Number of LEDs per Lamp:	14
Light Source Type:	LED
Cap/Socket:	G9
Color Temperature (K):	2700
Incandescent Equivalent:	19W
Luminous Flux (lm):	180
Color Rendering Index (CRI/Ra):	80
Colour Consistency (SDCM):	6
Average Life Time (h):	25000
Switch Cycles:	12500
Starting Time:	<0,5 s
Operational Temperature Min/Max:	-20° - +40°
Power Factor:	0.900000
Lamp Current (mA):	11
Lamp Effect (W):	2.3
Lamp Voltage (V):	220-240VAC
Energy Class:	A++



LED LAMP GY6,35 HALO-LED

344-29

LED-lamp with GY6,35 cap. This bulb is dimmable and the colour temperature is 2700K.

Specification **Logistical Information** **Documents**

Colour:	White
Light Source Color:	Warm white
Width/length (cm):	1.30
Height (cm):	4.60
Depth (cm):	1.30
Number of Lamps:	1
Number of LEDs per Lamp:	26
Light Source Type:	LED
Cap/Socket:	GY6,35
Color Temperature (K):	2700
Incandescent Equivalent:	24W
Luminous Flux (lm):	235
Color Rendering Index (CRI/Ra):	80
Colour Consistency (SDCM):	<6
Average Life Time (h):	25000
Switch Cycles:	12500
Starting Time:	0 s
Operational Temperature Min/Max:	-20° - +40°
Power Factor:	0.600000
Lamp Current (mA):	275
Lamp Effect (W):	2
Lamp Voltage (V):	12VAC/DC
Energy Class:	A++
IP Class:	IP20