



STEFCO A/S
Industrivej 3

8586 Ørum Djurs
Tlf. 86 38 18 50

LINK SEAL TÆTNINGER FOR DE MEST ANVENDTE RØRTYPER

STÅLRØR				RUSTFRIE STÅLRØR				PVC-, PE-, PP-RØR			
RØR Ø	BOREHUL	ANTAL LED	TYPE	RØR Ø	BOREHUL	ANTAL LED	TYPE	RØR Ø	BOREHUL	ANTAL LED	TYPE
17,2	50-54	4	LS-275	17	50-54	4	LS-275	16	48-55	4	LS-275
21,3	54-60	5	LS-275	20	53-58	5	LS-275	20	52-59	5	LS-275
26,9	59-61	5	LS-275	22	55-60	5	LS-275	25	57-62	5	LS-275
33,7	67-70	6	LS-275	35	69-74	7	LS-275	32	64-71	6	LS-275
42,4	75-77	7	LS-275	44	77-82	8	LS-275	40	73-79	7	LS-275
48,3	86-91	5	LS-300	54	87-93	9	LS-275	50	93-102	6	LS-315
60,3	94-98	10	LS-275	69	106-113	7	LS-300	63	95-102	10	LS-275
76,1	115-120	8	LS-300	84	122-127	8	LS-300	75	118-127	8	LS-315
88,9	127-130	9	LS-300	104	141-148	10	LS-300	90	126-134	9	LS-300
101,6	145-150	10	LS-315	114	166-180	11	LS-340	110	146-154	10	LS-300
108,0	152-158	11	LS-315	129	166-173	12	LS-300	125	168-176	12	LS-315
114,3	158-164	11	LS-315	139	190-198	7	LS-325	140	179-183	13	LS-300
133,0	202-214	10	LS-360	154	202-212	7	LS-325	160	197-203	14	LS-300
139,7	207-220	10	LS-360	168	245-255	7	LS-400	180	238-250	7	LS-425
159,0	225-240	11	LS-360	204	254-263	9	LS-325	200	249-258	9	LS-325
168,3	242-255	7	LS-400	219	267-275	10	LS-325	225	274-283	10	LS-325
219,1	294-305	9	LS-400	254	328-340	10	LS-400	250	298-307	11	LS-325
273,0	358-367	15	LS-475	273	350-363	11	LS-400	280	328-337	12	LS-325
323,9	398-412	12	LS-400	304	380-392	12	LS-400	315	368-373	14	LS-325
355,6	439-448	18	LS-475	323	397-412	12	LS-400	355	405-412	15	LS-325
406,4	481-495	15	LS-400	355	414-427	13	LS-425	400	450-457	17	LS-325
457,0	530-545	17	LS-400	406	480-495	15	LS-400	450	530-540	17	LS-400
508,0	620-632	18	LS-525	506	580-590	18	LS-400	500	575-585	18	LS-400
559,0	680-700	20	LS-500	606	680-693	22	LS-400	560	637-650	20	LS-400
610,0	693-704	30	LS-475	708	785-795	25	LS-400	630	705-718	23	LS-400
660,0	773-783	23	LS-525	808	865-895	29	LS-400	670	745-757	24	LS-400
711,2	825-835	24	LS-525	910	970-980	32	LS-425	710	785-795	25	LS-400
762,0	875-885	26	LS-525	1010	1085-1095	35	LS-400	800	875-885	28	LS-400
812,8	936-950	28	LS-500					900	975-985	32	LS-400
914,4	1030-1037	31	LS-525					1000	1075-1085	35	LS-400