



**General notes**

- This drawing indicates the overall layout of the new cast bronze fountain in Nygardsparken, Bergen.
- All design liability for the foundations, granite base, basin edge and waterproofing of the historic pool lies with The Municipality of Bergen.
- All details and drawings to be read in close conjunction with the Client's Specification.
- Bronze Foundry to allow for a full size pattern including all details to be presented to the Client for approval prior to manufacture.
- Bronze Foundry to make all necessary calculations regarding shrinkage of bronze elements in order to ensure that the final casting sizes accord with the digital 3D Model.
- Bronze Foundry to allow for any additional modelling that may be required in the workshop.
- Please note that there will be a Contractor's Design Portion to be undertaken by the Bronze foundry in the final design of the fixings which should be confirmed with the Client prior to manufacture.
- Final thickness and bronze composition to be agreed with the Client prior to casting.
- Pump to be located outside of the perimeter of the granite base to allow access and maintenance.
- All drilling and fixing into stone to be done by stonemasons.
- Coordination between the Bronze Foundry, stonemasons and plumbers will be required prior to and during installation on site.

**TENDER**

**ARKITEKT  
AKSEL ERVIK**

VESTRÅPPYRGEN 1683, 6750 STADLANDET  
TELEFON: +47 57000911 EMAIL: ARKITEKT@AKSELERVIK.NO  
NO 046 NO: 583 583 583 BIA NO: 3841935

PROJECT: FOUNTAIN, NYGAARDSPARKEN  
TITLE: FOUNTAIN REGION  
STATUS: FOR INFORMATION ONLY  
DRAWING NO: 001  
DATE: AUGUST 2023  
REVISION: A  
SCALE: 1/5, 1/10, 1/20, 1/100 ØA1

A | 18.10.2022 | Drawing updated to include site levels, general notes and tender annotations  
REV. | DATE | NOTES

CHECK ALL DIMENSIONS CAREFULLY ON SITE AND REPORT ANY DISCREPANCIES DO NOT SCALE FROM THIS DRAWING (EXCEPT PLANNING DRAWINGS)