



Laminate plan				
Outside:	Material:	No of plies:	Thickness:	Comments:
	Gelcoat	1	min. 0,5 mm	RAL 9010/9005 (GU25)
	CSM 450	1		Skincoate
	CSM 450	2		Vacuum
	DBLT 1200	7		Vacuum
Inside:	Topcoat	1	min. 0,5	RAL 7035
	Total:		8 mm	Vekt ca 120 kg

Monteringsplate for el utstyr  
20 mm kjerne med laminat  
(500x500 mm)

This drawing is our property.  
It can't be reproduced  
or communicated without  
our written agreement.

Litus Lux



KYSTVERKET

DRAWN BY <b>E.Flister</b>	DATE 07.01.2015
CHECKED BY <b>CR/AH</b>	DATE 08.01.2015
DESIGNED BY <b>P.E.Ose</b>	DATE 05.01.2015

DRAWING TITLE Panel 1/3		SIZE A2	DRAWING NUMBER 1138. 101	REV X
SCALE 1:20	WEIGHT(kg)	SHEET 1/11		