



TECHNICAL DATA SHEET

ECOFILL REBOUND

REV. 00 - 07/2016

<u>PROPERTIES</u>	<u>TEST METHODS</u>	<u>UNIT OF MEASURE</u>	<u>VALUES RESULTING FROM PRODUCTION CONTROLS</u>
Composition of polymeric material	-	-	100 % TPE granules
Colour	EN 14955	-	green
Particle shape	EN 14955	-	A2 - B3
Particle size	EN 933-1	mm	0,5 ÷ 2,5
Loose bulk density (untamped)	EN 1097-3	g/cm ³	0,46 ± 15 %
Heavy metals migration	EN 71-3	mg/Kg	in conformity to requirements of Category III
Heavy metals content	EPA	mg/Kg	tested
Polycyclic aromatic hydrocarbons (PAH)	ISO 18287	mg/Kg	in conformity to Commission Regulation (EU) N. 1272/2013
Polycyclic aromatic hydrocarbons (PAH)	EPA	mg/Kg	tested

Mondo keeps the right to modify the characteristics of the products in any moment.