



-EMPTYING PIPES TO BE LOCATED IN DOUBLE BOTTOM/PIPE TRUNK.  
-FILLING PIPES TO BE LOCATED BELOW MAIN DECK,- AS HIGH AS POSSIBLE.

PIPE DIM.: d 114,3x8 G1St (DN100)  
THROUGH F.O. TANKS: d 114,3 x 8 St (Black Steel)

— FILLING LINE  
- - - EMPTYING LINE

	21 PCS. BUTTERFLY VALVE
	3 PCS. MUD BOX
	2 PCS. 4" DIA. LAUX Model 42 type KE

This drawing is the property of Skipsteknik AS and must neither be used, reproduced nor handed over to any third party without our written consent.

REV:	DESCRIPTION:	DATE APPR.:	DATE REV.:	SIGN:
A	REVISED ACC. TO COMMENTS		11.10.05	FLO
B	REVISED ACC. TO DECK ARR. MUDBOX ADDED ACC. TO OWNERS		14.10.05	FLO

ORDER: **GRYFIA** 301-II A1

TITLE: **ORO PIPE SYSTEM**

SCALE: 1:1 DATE: 03.10.05

PROJECT NO.: 2004051

DRAWING NO.: 301-II-350-001-B

**SKIPSTEKNISK AS**  
CONSULTING NAVAL ARCHITECTS AND MARINE ENGINEERS  
Klaus Nilsenvegt. 4, P.O.Box 36, Sentrum, N-5001 Alesund  
Tel:+47 70 10 33 44, Telefax:+47 70 10 33 48  
E-mail: office@skipsteknik.no