

Merknad

Utføres i hht til NEK EN 60439-1

Det skal være min. 30% reserveplass i tavlen.

-

Har benyttet tverrfaglig merkesystem TFM.

-KW Kabel mellom 50 og 1000V

-KX Kabel > 50V

-

Symbolforklaring:

	JORDFEILAUTOMAT 30mA
	AUTOMATSIKRING
	EFFEKTBYTER
	LASTSKILLEBYTER
	KONTAKTOR
	OVERSPENNINGSVERN
	VARMEKABEL STYRING

-	-	-	-	-
-	-	-	-	-
-	-	-	-	-
-	-	-	-	-
Rev.	Dato	Revideringen gjelder	Saksb.	Sidem.k.

Statsbygg

Underfordeling snøsmelteanlegg

433.501

Nordnorsk kunstmuseum

Data

Spenning:	230V	IK-eff.verdi maks:	27, 6 kA
Frekvens:	50Hz	IK -eff.verdi min:	1,9 kA
Ford.system:	IT	Formkrav:	-
Hovedstrøm:	63A	Montasjeenhet:	-
Kapsling:	-	Hovedtilførsel:	-

Status

Tilbudstegning

COWI

Stakkevollveien 41
P.b. 3636 Guleng
9278 TROMSØ
02694



Oppdragsnr.	Målestokk	%	Tegnet av	krme	
Dato	11.01.2018	Saksbehandler	Sidemannskont.		
		krme			
Tegningsnummer	E-03			Rev.	-