

## Merknad

Utføres i hht til NEK EN 60439-1

Det skal være min. 30% reserveplass i tavlen.

-

Har benyttet tverrfaglig merkesystem TFM.

-KW Kabel mellom 50 og 1000V

-KX Kabel > 50V

-

## Symbolforklaring:

	JORDFEILAUTOMAT 30mA
	AUTOMATSIKRING
	EFFEKTBRUYTER
	LASTSKILLEBRUYTER
	KONTAKTOR
	OVERSPENNINGSVERN
	VARMEKABEL STYRING

-	-	-	-	-
-	-	-	-	-
-	-	-	-	-
-	-	-	-	-
Rev.	Dato	Revideringen gjelder	Saksb.	Sidem.k.

## Statsbygg

Underfordeling utendørs varmekabler  
433.20 eksisterende tavle  
Nordnorsk kunstmuseum

## Data

Spenning:	230V	IK-eff.verdi maks:	34,6 kA
Frekvens:	50Hz	IK -eff.verdi min:	20,3 kA
Ford.system:	IT	Formkrav:	-
Hovedstrøm:	250A	Montasjeenhet:	-
Kapsling:	-	Hovedtilførsel:	-

Status

Tilbudstegning

# COWI

Stakkevollveien 41  
P.b. 3636 Guleng  
9278 TROMSØ  
02694



Oppdragsnr.	Målestokk	Tegnet av
Dato	Saksbehandler	Sidemannskont.
Tegningsnummer	Rev.	
E-04	-	